

ITEM 550

EXISTING FENCING AND GATES

550.1 Description. This item shall govern for the removal of existing fencing and gates and their disposal, salvaging or reinstallation at a location as shown on the drawings or directed by the Engineer.

550.2 Construction Methods. Fencing which is not be reinstalled shall be removed from the site and disposed of by the Contractor unless salvaged as directed by the Engineer. All holes left as a result of post removal, if in an area not to receive roadway construction, excavation or fill, shall be filled and tamped with dirt to the elevation of natural ground. The Contractor shall provide the dirt.

When a chain link fence is to be reinstalled it shall be installed in accordance with the Item 555, "Chain Link Fencing". When barbed wire fence is to be reinstalled, it shall be reinstalled in accordance with the Item 556, "Four Strand Barbed Wire Fence". When wood fencing is to be reinstalled, it shall be reinstalled in accordance with the Item 554, "Wood Fencing".

When an existing fence is to be reinstalled, it shall be reinstalled with the same post spacing as the original, or as otherwise directed by the Engineer.

If a wood fence is to be reinstalled, the reinstallation shall be accomplished with new galvanized nails.

If a barbed wire fence is to be reinstalled, the reinstallation shall be accomplished with galvanized staples.

If a chain link fence is to be reinstalled, the reinstallation shall be accomplished with new galvanized pig rings or wire clips.

All new gates shall be as shown on the plans, or as directed by the Engineer. New gates shall be paid for under Items 554, 555 and 556, as appropriate.

550.3 Measurement. Measurement for the removal of existing fencing, the removal and salvage or the removal and reinstallation shall be made by the linear foot, including gates.

550.4 Payment. Payment shall be made at the contract unit price bid per linear foot of fencing, including gates:

- A. To be removed and disposed of;
- B. To be removed and salvaged;
- C. To be removed and re-installed;

and this unit price shall include all labor, equipment, and new materials necessary for removal and disposal, removal and salvaging, and/or reinstallation, necessary to complete the work.

There are line code(s), description(s) and unit(s) for this item.

NOTE: This specification requires other Standard Specifications

Item 554, Wood Fencing

Item 555, Chain Link Fencing

Item 556, Four Strand Barbed Wire Fence

END OF ITEM 550