

ITEM 551

CLEARING, GRUBBING AND FENCING

- 551.1 Description. This item shall consist of clearing and grubbing all trees, rubbish and/or grubbing the roadway right of way and erecting fences as shown on the plans and as required by these specifications.
- 551.2 Materials. Materials shall conform to the items, "Wood Fencing", "Chain Link Fencing", or "Four Strand Barbed Wire Fence".
- 551.3 Special Requirements. All bidders are required to visit the job site prior to submitting a bid for this work, in order to become fully acquainted with all job site conditions. Harris County will stake the right of way.
- The Contractor shall not impede, ingress or egress to private property or to motorist on the road during the entire term of the contract.
- At such locations where new fencing is to be installed and existing fencing removed, the existing fence shall not be removed until after new fencing has been installed.
- 551.4 Construction. Clearing and Grubbing shall be done in accordance with the item "Clearing and Grubbing". Fence removal shall be done in accordance with the item "Fence Removal". Fence erection shall be done in accordance with the Items, "Wood Fencing", "Chain Link Fencing", or "Four Strand Barbed Wire Fence".
- 551.5 Measurement and Payment. Clearing and Grubbing shall be measured and paid for in accordance with the Item "Clearing and Grubbing". Fence removal shall be measured and paid for in accordance with the Item "Existing Fencing and Gates". Treated timber shall be properly disposed of per current environmental regulations. Fence construction shall be measured and paid for in accordance with the Items, "Wood Fence", "Chain Link Fencing", or "Four Strand Barbed Wire Fence".

There are no line code(s), description(s), or unit(s) for this item.

END OF ITEM 551