

ITEM 560

MAINTENANCE AND CLEANUP OF THE PROJECT SITE

560.1 Description. This item shall govern for the maintenance and cleanup of the jobsite both during the term of the construction and at the end of construction.

560.2 General Requirements. The Contractor is required to remove from the job site all trash, excess materials, etc., accumulated as a result of and during this work.

At such time (daily or weekly) as directed by the Engineer, the Contractor shall remove any debris, trash or excess material off the site. He shall make every effort to keep the site in a neat, presentable condition, at all times.

In addition, at the end of each month, the entire construction site shall be generally cleaned and all trash and material over the length of the site shall be removed off site to the complete satisfaction of the Engineer.

The Contractor will mow, trim and edge the right-of-way and esplanades on the project for the entire project duration. The mowing schedule shall be as follows:

<u>April – October:</u>	<u>Once per month</u>
<u>November – March:</u>	<u>Once every six weeks</u>

After the construction work has been completed, the Contractor shall remove all debris, trash, excess materials, forms, stakes, empty sacks etc. from the site and leave the site with a neat appearance. All excavation shall be backfilled and all excess excavated material shall be disposed of off the site of the work.

560.3 Measurement and Payment. There shall be no separate payment for this item.

There are line code(s), description(s), and unit(s) for this item.

END OF ITEM 560