

ITEM 537

WHEEL STOPS

- 537.1 Description. This Item shall govern for the construction, furnishing and installing of precast reinforced concrete wheel stops.
- 537.2 Materials. Concrete shall be Class "C1" concrete and conform to Item 421 "Structural Concrete", while reinforcement shall conform to Item 440 "Reinforcing Steel".
- 537.3 Construction. Wheel stops shall be constructed in accordance with the Standard Civil Drawing.
- 537.4 Measurement. Wheel stops shall be measured by each unit, which shall include attachment pins (No.4 Grade 60 reinforcing bars, 12 inches in length with 7 inch embedment depth), furnished and installed.
- 537.5 Payment. Wheel stop shall be paid for at the contract unit price for each unit, furnished and installed in place. This price shall be full compensation for all materials, equipment and labor necessary to furnish and install the wheel stop.

There are line code(s), description(s), and unit(s) for this Item.

NOTE: This Item requires a Standard Civil Drawing that shall be incorporated into the contract documents.

NOTE: This Item requires other Standard Specifications.

421 "Structural Concrete"
440 "Reinforcing Steel"

END OF ITEM 537